

鋼管杭工 数量表

工程	規格	単位	杭NO.																																												合計	備考				
			1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44						
上杭長		m	7.0	4.5	6.0	4.0	7.5	5.0	7.0	7.5	7.5	8.0	6.0	5.0	7.0	3.0	6.0	5.0	3.5	6.0	4.0	6.0	4.5	6.0	4.5	6.0	4.0	7.5	3.5	7.0	6.0	4.0	6.0	3.5	6.5	3.0	4.0	6.0	3.0	4.5	6.0	8.0	3.0	6.0	3.5	6.0	237.5					
中杭長		m											4.0	7.0	8.0	8.0	5.5	8.0	8.0	7.0	8.0	7.5	8.0	8.0	8.0	7.5	8.0	8.0	8.0	5.0	8.0	4.5	8.0	8.0	7.0	7.0	3.5	8.0	4.5	6.5		8.0					212.5					
下杭長		m		4.0	3.5	6.5	4.0	8.0	8.0	8.0	7.5	7.5	7.0	6.5	4.0	8.0	7.5	6.5	8.0	7.0	8.0	7.0	8.0	7.0	8.0	6.5	8.0	4.0	8.0	4.0	8.0	7.0	8.0	7.0	4.0	8.0	7.0	8.0	6.5	8.0	4.0	8.0	4.0	7.5	8.0	3.5	286.5					
杭全長		m	7.0	8.5	9.5	10.5	11.5	13.0	15.0	15.5	15.0	15.5	17.0	18.5	19.0	19.0	19.0	19.5	19.5	20.0	20.0	20.5	20.5	21.0	20.5	20.0	20.0	19.5	19.5	19.0	19.0	19.0	18.5	18.5	18.5	18.0	18.0	17.5	17.5	17.0	16.5	16.0	15.0	13.5	11.5	9.5	736.5					
杭材(L=6.0~12.0)	SKK 400材 d508 t24.0	t	2.005		1.719	1.862	2.148	2.292	4.297	4.440	4.297	4.440	3.724	3.867	4.297	4.583	3.867	4.154	4.583	5.729	4.583	5.872	4.583	6.015	4.583	5.729	4.583	4.440	4.583	4.297	4.010	4.297	4.010	4.297	4.154	4.297	4.010	4.010	4.154	2.292	3.581	4.583	2.292	3.867	2.292	1.719	169.437					
杭材(L=3.0~5.9)	SKK 400材 d508 t24.0	t		2.435	1.003	1.146	1.146	1.432					1.146	1.432	1.146	0.859	1.575	1.432	1.003		1.146		1.289		1.289		1.146	1.146	1.003	1.146	1.432	1.146	1.289	1.003	1.146	0.859	1.146	1.003	0.859	2.578	1.146		2.005		1.003	1.003	41.538					
継手		箇所		1	1	1	1	1	1	1	1	1	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	1	2	1	1	1	73		
吊り穴加工		箇所	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	88	
吊り金具		枚		2	2	2	2	2	2	2	2	2	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	2	4	2	2	2	146		
注入管		m	14.0	17.0	19.0	21.0	23.0	26.0	30.0	31.0	30.0	31.0	34.0	37.0	38.0	38.0	38.0	39.0	39.0	40.0	40.0	41.0	41.0	42.0	41.0	40.0	40.0	39.0	39.0	38.0	38.0	38.0	37.0	37.0	37.0	36.0	36.0	35.0	35.0	34.0	33.0	32.0	30.0	27.0	23.0	19.0	1473.0					
注入管、エルボ		ヶ	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	88		
注入管、ソケット		ヶ	2	2	2	2	4	4	4	4	4	4	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	4	4	4	4	4	4	2	222		
大口径ボーリング工	φ550 レキ質土	m	1.9	3.2	4.2	5.0	6.1	8.0	9.9	10.2	10.0	10.1	11.7	13.4	13.9	13.7	13.6	14.0	14.4	14.7	15.0	15.2	15.4	15.6	15.3	15.0	14.7	14.4	14.1	13.9	13.7	13.5	13.4	13.3	13.1	13.0	12.7	12.5	12.2	11.9	11.4	10.6	9.8	8.1	6.2	4.1	506.1					
大口径ボーリング工	φ550 軟岩(Ⅱ)	m	5.1	5.3	5.3	5.5	5.4	5.0	5.1	5.3	5.0	5.4	5.3	5.1	5.1	5.3	5.4	5.5	5.1	5.3	5.0	5.3	5.1	5.4	5.2	5.0	5.3	5.1	5.4	5.1	5.3	5.5	5.1	5.2	5.4	5.0	5.3	5.0	5.3	5.1	5.1	5.4	5.2	5.4	5.3	5.4	5.3	5.4	230.4			
削孔全長		m	7.0	8.5	9.5	10.5	11.5	13.0	15.0	15.5	15.0	15.5	17.0	18.5	19.0	19.0	19.0	19.5	19.5	20.0	20.0	20.5	20.5	21.0	20.5	20.0	20.0	19.5	19.5	19.0	19.0	19.0	18.5	18.5	18.5	18.0	18.0	17.5	17.5	17.0	16.5	16.0	15.0	13.5	11.5	9.5	736.5					
充填材料	モルタル	m3	1.829	2.221	2.483	2.744	3.005	3.397	3.920	4.051	3.920	4.051	4.443	4.835	4.965	4.965	4.965	5.096	5.096	5.227	5.227	5.357	5.357	5.488	5.357	5.227	5.227	5.096	5.096	4.965	4.965	4.965	4.835	4.835	4.835	4.704	4.704	4.573	4.573	4.443	4.312	4.181	3.920	3.528	3.005	2.483	192.471					